Task	Responsibility and Information Flow	Notes
Review contractor completion submittals as required by contract documents  Typical documents include:  Municipal occupancy permit  As-built documents, showing changes made during construction  Final Clearance Certificate from the respective provincial or territorial health	General contractor to architect and consultants	Architect and consultants as appropriate review the documents and architect submits them to the owner with comments or recommendations regarding their conformity with the contract requirements.
<ul> <li>and safety agencies</li> <li>Statutory Declarations for application for release of holdback from the general contractor and all subcontractors</li> <li>Final reports on work carried out to correct deficiencies</li> <li>A list of all contractors and trade subcontractors</li> <li>Replacement materials, maintenance products, special tools, etc.</li> </ul>		
<ul> <li>Manuals incorporating:</li> <li>Maintenance and operating instructions</li> <li>All warranties for materials, equipment and products</li> <li>Copies of all the permits and certificates of authorization issued by the various public utilities companies and authorities having jurisdiction</li> </ul>		
Arrange for appropriate personnel to attend demonstration(s) of systems, including takeover of applicable operating systems and instructions  Obtain appropriate records of demonstration and operation.	General contractor	
<ul> <li>Substantial Performance</li> <li>Receive from the contractor an application for Certificate of Substantial Performance and list of items to be completed or corrected</li> </ul>	General contractor to architect and consultants	Note: Substantial performance review time frames read differently in CCDC 2 versus <i>RAIC Document Six</i> .