

Task	Responsibility and Information Flow	Notes
<p>Division 25 – Integrated Automation</p> <ul style="list-style-type: none"> ▪ testing of controls <p>Division 26 – Electrical</p> <ul style="list-style-type: none"> ▪ testing of emergency lighting and ▪ emergency power supply <p>Division 27 – Communications</p> <ul style="list-style-type: none"> ▪ testing of communications systems <p>Division 28 – Electronic Safety and Security</p> <ul style="list-style-type: none"> ▪ verification of fire alarm system <p>Division 31 – Earthwork</p> <ul style="list-style-type: none"> ▪ additional geotechnical reports ▪ soil-bearing capacity ▪ approval of backfilling materials ▪ compaction of soils or fill ▪ load tests on, and inspections of, piles and caissons ▪ inspection of underpinning and shoring ▪ inspection of soil stabilization 		
<p>Testing of complete systems, such as the building envelope, interior air quality, or integrated electrical and communications systems may also be required</p>		